



3.1.22

RE: ABSF Roller Ski Loop RFP

The American Birkebeiner Ski Foundation is seeking bids to construct an approx. 5km paved roller ski loop at Mt. Telemark Village. The specifications are laid out below and a map of the project is included.

Specifications

Estimates for base course should follow specs

- grade subsurface
- provide and place 4" compacted 1 1/4 minus base course
- estimated distance of 14,400' at 10' wide
- estimated distance of 1,800' at 15' wide
- finish grade to within .10ft
- final price determined by units used x unit pricing

Estimates for asphalt should follow specs

- fine grade, water, compact
- provide and place 2" pavement
- Pavement mix 4LT 58-28S
- estimated distance of 14,400' at 10' wide
- estimated distance of 1,800' at 15' wide
- final pricing determined by units used x unit pricing

Questions or to submit a proposal and timeline contact:

Jim Sokup
Director of Facilities
10527 Main St.
Hayward, WI 54843
Jim.Sokup@birkie.com
715.634.5025

Project to begin summer of 2022 with completion by fall of 2022.